

ST.MARTHA'S SPECIAL SCHOOL FOR THE MENTALLY CHALLENGED Kalpana Road, Chittattumukku P.O. Menamkulam, Trivandrum – 695 301 Reg.No: SJD/1410/2021-D8, Phone: 0471/2705 764 - 9388084403 Email: <u>stmarthaspecialschool@gmail.com</u>

Date:14/12/2023

## **Short Quotation Notice**

Sealed quotations are invited for the supply of the following materials for the Sensory Park having prescribed specification and quality for St. Martha's Special School. Last date for the submission of tender will be on 31th December 2023,10.45 AM and the same will be opened by 11.45 AM on the same day. The participants should provide the detailed specification along with the quoted price along with GST, transportation and service charge. The decision of the Manager is final and she has the right to reject the quotation if the items supplied by the agency found to be substandard or not meet technical specification.

Sincerely

Sp. Soss Sr. Sossy Abraham

(Manager)





ST.MARTHA'S SPECIAL SCHOOL FOR THE MENTALLY CHALLENGED Kalpana Road, Chittattumukku P.O. Menamkulam, Trivandrum – 695 301 Reg.No: SJD/1410/2021-D8, Phone: 0471/2705 764 - 9388084403 Email: <u>stmarthaspecialschool@gmail.com</u>

Date:14/11/2023

## **Short Quotation Notice**

Sealed quotations are invited for the supply of the following materials for the Sensory Park having prescribed specification and quality for St. Martha's Special School. Last date for the submission of tender will be on 10th December 2023,10.45 AM and the same will be opened by 11.45 AM on the same day. The participants should provide the detailed specification along with the quoted price along with GST, transportation and service charge. The decision of the Manager is final and she has the right to reject the quotation if the items supplied by the agency found to be substandard or not meet technical specification.

Sincerely

r. Sorrg

Sr. Sossy Abraham

(Manager)



## **TENDER DOCUMENT**

## PROJECT NAME: PROPOSED CONSTRUCTION OF SENSORY PARK FOR ST. MARTHA'SSPECIAL SCHOOL, KALPANA ROAD, CHITTATTUMUKKU P.O, TRIVANDRUMDISTRICT.

<b>OWNER : THE CORRESPONDENT</b>							
Sl. No	Description	Quantity	Unit	Rate/unit	Amount		
1	Removing the debris and level the ground as good for construction as per the direction of engineer incharge (or) Owner.		LS				
2	Supplying and laying interlocks to make path way, over the coarse aggregate bed of 6mm metal of 12mm thick, in correct line and levels and make good as per the direction of Owner.	1151.17	Sq.ft				
3	36mm Color Rubber Flooring : (30mm Base Cushion Rubber + 6mm Top Color Rubber) Laying of Rubber Kids play area safety flooring with total thickness 36mm; of which 30mm black base cushion rubber in thread form called as BUFFING with PU BINDER CHEMICAL 15% for strong bonding and top 6mm RUBBER colored Granules (Size - 1mm to 4mm) with PU BINDER CHEMICAL 20% to 22% for strong Bonding(PU raw material imported from Germany of BASF/DOW/HUNTSMAN; processed in INDIA)	1111.90	Sq.ft				
4	Supplying and laying Polycarbonate sheet 3mm thickness over the park area with required slope and required rain water pathway without any leakage and as per the direction of Owner.	2404.86	Sq.ft				

5	Applying two coat of exterior quality paint over boundary walls and making arts over walls as per the direction of Owner		LS	
6	Supplying and fixing JUNGLE PLAYCENTRE	1.00	NO	
7	Supplying and fixing TWIST CLIMBER	1.00	NO	
8	Supplying and fixing Xylophone	1.00	NO	
9	Supplying and fixing Benches and statues as per the direction of Owner. (Numbers as per Drawing)			
	Benches	3.00	NO	
	Statues	6.00	NO	
10	LandScaping Work		LS	
11	Supplying and fixing Cradle		LS	
12	Electrical Works		LS	
13	Flooring by PCC 1:4:8 (1 Cement : 4 sand : 8 Metal) in correct line and levels including cost of all materials and labours etc complete		LS	
14	Supplying and fixing Fountain		LS	
15	Supplying and fixing the ORB		NO	
16	Supplying and fixing stainless steel hand rails		NO	
	TOTAL AMOUNT			1